

**PLANNING COMMISSION – September 9, 2020
CONDITIONS OF APPROVAL**

**15925 Quail Hill Road
Architecture and Site Application S-19-012**

Requesting approval for demolition of an existing single-family residence and detached accessory dwelling unit, and construction of a two-story single-family residence on property zoned HR-1. APN 527-02-007.

**PROPERTY OWNER: John and Allison Diep
APPLICANT: Gary Kohlsaat.**

TO THE SATISFACTION OF THE DIRECTOR OF COMMUNITY DEVELOPMENT:

Planning Division

1. APPROVAL: This application shall be completed in accordance with all of the conditions of approval and in substantial compliance with the approved plans. Any changes or modifications to the approved plans and/or business operation shall be approved by the Community Development Director, DRC or the Planning Commission depending on the scope of the changes.
2. EXPIRATION: The approval will expire two years from the approval date pursuant to Section 29.20.320 of the Town Code, unless the approval has been vested.
3. MAXIMUM FLOOR AREA: The above grade floor area shall be reduced to no more than 5,100 square feet through a lowering of the floor level as described in the supplemental justification letter.
4. EXTERIOR COLOR: The individual exterior materials of the house, including the roof, shall not exceed a light reflectivity value of 30 and shall blend with the natural vegetation.
5. DEED RESTRICTION: Prior to the issuance of a building permit, a deed restriction shall be recorded by the applicant with the Santa Clara County Recorder's Office that requires all exterior materials to be maintained in conformance with the Town's Hillside Development Standards and Guidelines.
6. OUTDOOR LIGHTING: Exterior lighting shall be kept to a minimum and shall be downward directed and shielded fixtures that will not reflect or encroach onto adjacent properties. No flood lights shall be used unless it can be demonstrated that they are needed for safety or security.
7. TREE REMOVAL PERMIT: A Tree Removal Permit shall be obtained for any protected trees to be removed, prior to the issuance of a building or grading permit.
8. EXISTING TREES: All existing trees shown on the plan and trees required to remain or to be planted are specific subjects of approval of this plan and must remain on the site.

9. TREE FENCING: Protective tree fencing, and other protection measures shall be placed at the drip line of existing trees prior to issuance of demolition and building permits and shall remain through all phases of construction. Include a tree protection plan with the construction plans.
10. TREE STAKING: All newly planted trees shall be double-staked using rubber tree ties.
11. FRONT YARD LANDSCAPE: Prior to issuance of a Certificate of Occupancy the front yard must be landscaped.
12. ARBORIST REQUIREMENTS: The developer shall implement, at their cost, all recommendations identified in the Arborist's report. These recommendations must be incorporated in the building permit plans and completed prior to issuance of a building permit where applicable. A Compliance Memorandum shall be prepared by the applicant and submitted with the building permit application detailing how the recommendations have or will be addressed.
13. WATER EFFICIENCY LANDSCAPE ORDINANCE: The final landscape plan shall meet the requirements of the Town of Los Gatos Water Conservation Ordinance or the State Water Efficient Landscape Ordinance, whichever is more restrictive. Submittal of a Landscape Documentation Package pursuant to WELO is required prior to issuance of a building permit. A review fee based on the current fee schedule adopted by the Town Council is required when working landscape and irrigation plans are submitted for review. A completed WELO Certificate of Completion is required prior to final inspection/certificate of occupancy.
14. STORY POLES: The story poles on the project site shall be removed within 30 days of approval of the Architecture & Site application.
15. TOWN INDEMNITY: Applicants are notified that Town Code Section 1.10.115 requires that any applicant who receives a permit or entitlement from the Town shall defend, indemnify, and hold harmless the Town and its officials in any action brought by a third party to overturn, set aside, or void the permit or entitlement. This requirement is a condition of approval of all such permits and entitlements whether or not expressly set forth in the approval and may be secured to the satisfaction of the Town Attorney.
16. COMPLIANCE MEMORANDUM: A memorandum shall be prepared and submitted with the building plans detailing how the Conditions of Approval will be addressed.

Building Division

17. PERMITS REQUIRED: A Demolition Permit is required for the demolition of each existing structure. A separate Building Permit is required for the construction of the new single-family residence and attached garage. Other detached structures such as pool houses, accessory dwelling units, pools, or retaining walls will require individual Building Permits.
18. APPLICABLE CODES: The current codes, as amended and adopted by the Town of Los Gatos as of January 1, 2020, are the 2019 California Building Standards Code, California Code of Regulations Title 24, Parts 1-12, including locally adopted Energy Reach Codes.
19. CONDITIONS OF APPROVAL: The Conditions of Approval must be blue lined in full on the cover sheet of the construction plans. A Compliance Memorandum shall be prepared and submitted with the building permit application detailing how the Conditions of Approval will be addressed.

20. BUILDING & SUITE NUMBERS: Submit requests for new building addresses to the Building Division prior to submitting for the building permit application process.
21. SIZE OF PLANS: Submit four sets of construction plans, minimum size 24" x 36", maximum size 30" x 42".
22. REQUIREMENTS FOR COMPLETE DEMOLITION OF STRUCTURE: Obtain a Building Department Demolition Application and a Bay Area Air Quality Management District Application from the Building Department Service Counter. Once the demolition form has been completed, all signatures obtained, and written verification from PG&E that all utilities have been disconnected, return the completed form to the Building Department Service Counter with the Air District's J# Certificate, PG&E verification, and three (3) sets of site plans showing all existing structures, existing utility service lines such as water, sewer, and PG&E. No demolition work shall be done without first obtaining a permit from the Town.
23. SOILS REPORT: A Soils Report, prepared to the satisfaction of the Building Official, containing foundation and retaining wall design recommendations, shall be submitted with the Building Permit Application. This report shall be prepared by a licensed Civil Engineer specializing in soils mechanics.
24. SHORING: Shoring plans and calculations will be required for all excavations which exceed five (5) feet in depth or which remove lateral support from any existing building, adjacent property, or the public right-of-way. Shoring plans and calculations shall be prepared by a California licensed engineer and shall confirm to the Cal/OSHA regulations.
25. FOUNDATION INSPECTIONS: A pad certificate prepared by a licensed civil engineer or land surveyor shall be submitted to the project Building Inspector at foundation inspection. This certificate shall certify compliance with the recommendations as specified in the Soils Report, and that the building pad elevations and on-site retaining wall locations and elevations have been prepared according to the approved plans. Horizontal and vertical controls shall be set and certified by a licensed surveyor or registered Civil Engineer for the following items:
 - a. Building pad elevation
 - b. Finish floor elevation
 - c. Foundation corner locations
 - d. Retaining wall(s) locations and elevations
26. TITLE 24 ENERGY COMPLIANCE: All required California Title 24 Energy Compliance Forms must be blue-lined (sticky-backed), i.e. directly printed, onto a plan sheet.
27. TOWN RESIDENTIAL ACCESSIBILITY STANDARDS: New residential units shall be designed with adaptability features for single-family residences per Town Resolution 1994-61:
 - a. Wood backing (2" x 8" minimum) shall be provided in all bathroom walls, at water closets, showers, and bathtubs, located 34 inches from the floor to the center of the backing, suitable for the installation of grab bars if needed in the future.
 - b. All passage doors shall be at least 32-inch wide doors on the accessible floor level.
 - c. The primary entrance door shall be a 36-inch-wide door including a 5'x 5' level landing, no more than 1 inch out of plane with the immediate interior floor level and with an 18-inch clearance at interior strike edge.
 - d. A door buzzer, bell or chime shall be hard wired at primary entrance.

28. BACKWATER VALVE: The scope of this project may require the installation of a sanitary sewer backwater valve per Town Ordinance 6.50.025. Please provide information on the plans if a backwater valve is required and the location of the installation. The Town of Los Gatos Ordinance and West Valley Sanitation District (WVSD) requires backwater valves on drainage piping serving fixtures that have flood level rims less than 12 inches above the elevation of the next upstream manhole.
29. HAZARDOUS FIRE ZONE: All projects in the Town of Los Gatos require Class A roof assemblies.
30. WILDLAND-URBAN INTERFACE: This project is located in a Wildland-Urban Interface High Fire Area and must comply with Section R337 of the 2019 California Residential Code, Public Resources Code 4291 and California Government Code Section 51182.
31. PROVIDE DEFENSIBLE SPACE/FIRE BREAK LANDSCAPING PLAN: Prepared by a California licensed Landscape Architect in conformance with California Public Resources Code 4291 and California Government Code Section 51182.
32. PRIOR TO FINAL INSPECTION: Provide a letter from a California licensed Landscape Architect certifying the landscaping and vegetation clearance requirements have been completed per the California Public Resources Code 4291 and Government Code Section 51182.
33. SPECIAL INSPECTIONS: When a special inspection is required by CBC Section 1704, the Architect or Engineer of Record shall prepare an inspection program that shall be submitted to the Building Official for approval prior to issuance of the Building Permit. The Town Special Inspection form must be completely filled-out and signed by all requested parties prior to permit issuance. Special Inspection forms are available from the Building Division Service Counter or online at www.losgatosca.gov/building.
34. BLUEPRINT FOR A CLEAN BAY SHEET: The Town standard Santa Clara Valley Nonpoint Source Pollution Control Program Sheet (page size same as submitted drawings) shall be part of the plan submittal as the second page. The specification sheet is available at the Building Division Service Counter for a fee of \$2 or at ARC Blueprint for a fee or online at www.losgatosca.gov/building.
35. APPROVALS REQUIRED: The project requires the following departments and agencies approval before issuing a building permit:
 - a. Community Development – Planning Division: (408) 354-6874
 - b. Engineering/Parks & Public Works Department: (408) 399-5771
 - c. Santa Clara County Fire Department: (408) 378-4010
 - d. West Valley Sanitation District: (408) 378-2407
 - e. Local School District: The Town will forward the paperwork to the appropriate school district(s) for processing. A copy of the paid receipt is required prior to permit issuance.

TO THE SATISFACTION OF THE DIRECTOR OF PARKS & PUBLIC WORKS:

Engineering Division

36. GENERAL: All public improvements shall be made according to the latest adopted Town Standard Plans, Standard Specifications and Engineering Design Standards. All work shall

conform to the applicable Town ordinances. The adjacent public right-of-way shall be kept clear of all job-related mud, silt, concrete, dirt and other construction debris at the end of the day. Dirt and debris shall not be washed into storm drainage facilities. The storing of goods and materials on the sidewalk and/or the street will not be allowed unless an encroachment permit is issued by the Engineering Division of the Parks and Public Works Department. The Owner and/or Applicant's representative in charge shall be at the job site during all working hours. Failure to maintain the public right-of-way according to this condition may result in the issuance of correction notices, citations, or stop work orders and the Town performing the required maintenance at the Owner and/or Applicant's expense.

37. APPROVAL: This application shall be completed in accordance with all the conditions of approval listed below and in substantial compliance with the latest reviewed and approved development plans. Any changes or modifications to the approved plans or conditions of approvals shall be approved by the Town Engineer.
38. CONSTRUCTION PLAN REQUIREMENTS: Construction drawings shall comply with Section 1 (Construction Plan Requirements) of the Town's Engineering Design Standards, which are [available for download from the Town's website](#).
39. ENCROACHMENT PERMIT: All work in the public right-of-way will require a Construction Encroachment Permit. All work over \$5,000 will require construction security. It is the responsibility of the Owner and/or Applicant to obtain any necessary encroachment permits from affected agencies and private parties, including but not limited to, Pacific Gas and Electric (PG&E), AT&T, Comcast, Santa Clara Valley Water District, California Department of Transportation (Caltrans). Copies of any approvals or permits must be submitted to the Town Engineering Division of the Parks and Public Works Department prior to releasing any permit.
40. PRIVATE IMPROVEMENTS IN THE PUBLIC RIGHT-OF-WAY (INDEMNITY AGREEMENT): The property owner shall enter into an agreement with the Town for all existing and proposed private improvements within the Town's right-of-way. The Owner shall be solely responsible for maintaining the improvements in a good and safe condition at all times and shall indemnify the Town of Los Gatos. The agreement must be completed and accepted by the Director of Parks and Public Works, and subsequently recorded by the Town Clerk at the Santa Clara County Office of the Clerk-Recorder, prior to the issuance of any grading or building permits. Please note that this process may take approximately six to eight (6-8) weeks.
41. PUBLIC WORKS INSPECTIONS: The Owner and/or Applicant or their representative shall notify the Engineering Inspector at least twenty-four (24) hours before starting any work pertaining to on-site drainage facilities, grading or paving, and all work in the Town's right-of-way. Failure to do so will result in penalties and rejection of any work that occurred without inspection.
42. RESTORATION OF PUBLIC IMPROVEMENTS: The Owner and/or Applicant or their representative shall repair or replace all existing improvements not designated for removal that are damaged or removed because of the Owner and/or Applicant or their representative's operations. Improvements such as, but not limited to: curbs, gutters, sidewalks, driveways, signs, pavements, raised pavement markers, thermoplastic

pavement markings, etc., shall be repaired and replaced to a condition equal to or better than the original condition. Any new concrete shall be free of stamps, logos, names, graffiti, etc. Any concrete identified that is displaying a stamp or equal shall be removed and replaced at the Contractor's sole expense and no additional compensation shall be allowed therefore. Existing improvement to be repaired or replaced shall be at the direction of the Engineering Construction Inspector and shall comply with all Title 24 Disabled Access provisions. The restoration of all improvements identified by the Engineering Construction Inspector shall be completed before the issuance of a certificate of occupancy. The Owner and/or Applicant or their representative shall request a walk-through with the Engineering Construction Inspector before the start of construction to verify existing conditions.

43. SITE SUPERVISION: The General Contractor shall provide qualified supervision on the job site at all times during construction.
44. STREET CLOSURE: Any proposed blockage or partial closure of the street requires an encroachment permit. Special provisions such as limitations on works hours, protective enclosures, or other means to facilitate public access in a safe manner may be required.
45. PLAN CHECK FEES: Plan check fees associated with the Grading Permit shall be deposited with the Engineering Division of the Parks and Public Works Department prior to the commencement of plan check review.
46. GRADING PERMIT FEES: All fees associated with the grading permit shall be deposited with the Engineering Division of the Parks and Public Works Department prior to the issuance of a grading permit.
47. DESIGN CHANGES: Any proposed changes to the approved plans shall be subject to the approval of the Town prior to the commencement of any and all altered work. The Owner and/or Applicant's project engineer shall notify, in writing, the Town Engineer at least seventy-two (72) hours in advance of all the proposed changes. Any approved changes shall be incorporated into the final "as-built" plans.
48. PLANS AND STUDIES: Any studies imposed by the Planning Commission or Town Council shall be funded by the Owner and/or Applicant. Grading permit plans shall be prepared by a Registered Professional Engineer in the State of California and submitted to the Town Engineer for review and approval.
49. GRADING PERMIT: A grading permit is required for all site grading and drainage work except for exemptions listed in Section 12.20.015 of The Code of the Town of Los Gatos (Grading Ordinance). After the preceding Architecture and Site Application has been approved by the respective deciding body, the grading permit application (with grading plans and associated required materials and plan check fees) shall be made to the Engineering Division of the Parks and Public Works Department located at 41 Miles Avenue. The grading plans shall include final grading, drainage, retaining wall location(s), driveway, utilities and interim erosion control. Grading plans shall list earthwork quantities and a table of existing and proposed impervious areas. Unless specifically allowed by the Director of Parks and Public Works, the grading permit will be issued concurrently with the building permit. The grading permit is for work outside the building footprint(s). Prior to Engineering signing off and closing out on the issued grading permit, the Owner and/or Applicant's soils engineer shall verify, with a stamped and signed letter, that the grading

activities were completed per plans and per the requirements as noted in the soils report. A separate building permit, issued by the Building Department, located at 110 E. Main Street, is needed for grading within the building footprint.

50. GRADING ACTIVITY RESTRICTIONS: Upon receipt of a grading permit, any and all grading activities and operations shall not commence until after/occur during the rainy season, as defined by Town Code of the Town of Los Gatos, Sec. 12.10.020, (October 15-April 15), has ended.
51. COMPLIANCE WITH HILLSIDE DEVELOPMENT STANDARDS AND GUIDELINES: All grading activities and operations shall be in compliance with Section III of the Town's Hillside Development Standards and Guidelines. All development shall be in compliance with Section II of the Town's Hillside Development Standards and Guidelines.
52. DRIVEWAY: The driveway conform to existing pavement on Drysdale Drive shall be constructed in a manner such that the existing drainage patterns will not be obstructed.
53. DRAINAGE IMPROVEMENT: Prior to the issuance of any grading or building permits, the Owner and/or Applicant shall: a) design provisions for surface drainage; and b) design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and c) provide a recorded copy of any required easements to the Town.
54. SURVEYING CONTROLS: Horizontal and vertical controls shall be set and certified by a licensed surveyor or registered civil engineer qualified to practice land surveying, for the following items:
 - a. Retaining wall: top of wall elevations and locations.
 - b. Toe and top of cut and fill slopes.
55. PRECONSTRUCTION MEETING: Prior to the commencement of any site work, the general contractor shall:
 - a. Along with the Owner and/or Applicant, attend a pre-construction meeting with the Town Engineer to discuss the project conditions of approval, working hours, site maintenance and other construction matters;
 - b. Acknowledge in writing that they have read and understand the project conditions of approval and will make certain that all project sub-contractors have read and understand them as well prior to commencing any work, and that a copy of the project conditions of approval will be posted on-site at all times during construction.
56. RETAINING WALLS: A building permit, issued by the Building Division, located at 110 E. Main Street, may be required for site retaining walls. Walls are not reviewed or approved by the Engineering Division of Parks and Public Works during the grading permit plan review process.
57. DEDICATIONS: The following shall be dedicated by separate instrument. The dedication shall be recorded before any grading or building permits are issued:
 - a. Landscape Easement as delineated on sheets C.4 through C.6 on the plans prepared by Hanna-Brunetti.
 - b. Wire Crossing Easement: 10 feet wide, centered along the line between the existing utility poles situated along the subject property's eastern boundary and located on the neighboring property to the west, granted by the property owners to their neighbor.

58. SOILS REVIEW: Prior to Town approval of a development application, the Owner and/or Applicant's engineers shall prepare and submit a design-level geotechnical and geological investigation for review by the Town's consultant, with costs borne by the Owner and/or Applicant, and subsequent approval by the Town. The Owner and/or Applicant's soils engineer shall review the final grading and drainage plans to ensure that designs for foundations, retaining walls, site grading, and site drainage are in accordance with their recommendations and the peer review comments. Approval of the Owner and/or Applicant's soils engineer shall then be conveyed to the Town either by submitting a Plan Review Letter prior to issuance of grading or building permit(s).
59. SOILS ENGINEER CONSTRUCTION OBSERVATION: During construction, all excavations and grading shall be inspected by the Owner and/or Applicant's soils engineer prior to placement of concrete and/or backfill so they can verify that the actual conditions are as anticipated in the design-level geotechnical report and recommend appropriate changes in the recommendations contained in the report, if necessary. The results of the construction observation and testing shall be documented in an "as-built" letter/report prepared by the Owner and/or Applicant's soils engineer and submitted to the Town before a certificate of occupancy is granted.
60. SOIL RECOMMENDATIONS: The project shall incorporate the geotechnical/geological recommendations contained in the Updated Geotechnical & Geological Investigation for Proposed New Residence by Pollak Engineering, Inc., dated September 13, 2019, and any subsequently required report or addendum. Subsequent reports or addendum are subject to peer review by the Town's consultant and costs shall be borne by the Owner and/or Applicant.
61. PUBLIC IMPROVEMENTS: The following improvements shall be installed by the Owner and/or Applicant. Plans for those improvements shall be prepared by a California registered civil engineer, reviewed and approved by the Town before the issuance of any grading or building permits or the recordation of a map. The improvements must be completed and accepted by the Town before a Certificate of Occupancy for any new building can be issued.
 - a. Drysdale Drive: 2" overlay from the centerline to the western lip of gutter, or alternative pavement restoration measure as approved by the Town Engineer.
 - b. Shady Lane: 2" overlay from the centerline to the southern lip of gutter/edge of pavement, or alternative pavement restoration measure as approved by the Town Engineer.
62. CERTIFICATE OF OCCUPANCY: The Engineering Division of the Parks and Public Works Department will not sign off on a Temporary Certificate of Occupancy or a Final Certificate of Occupancy until all required improvements within the Town's right-of-way have been completed and approved by the Town.
63. FRONTAGE IMPROVEMENTS: The Owner and/or Applicant shall be required to improve the project's public frontage (right-of-way line to centerline and/or to limits per the direction of the Town Engineer) to current Town Standards. These improvements may include but not limited to curb, gutter, sidewalk, driveway approach(es), curb ramp(s), signs, pavement, raised pavement markers, thermoplastic pavement markings, storm drain

facilities, etc. The improvements must be completed and accepted by the Town before a Certificate of Occupancy for any new building can be issued.

64. UTILITIES: The Owner and/or Applicant shall install all new, relocated, or temporarily removed utility services, including telephone, electric power and all other communications lines underground, as required by Town Code Section 27.50.015(b). All new utility services shall be placed underground. Underground conduit shall be provided for cable television service. The Owner and/or Applicant is required to obtain approval of all proposed utility alignments from any and all utility service providers before a Certificate of Occupancy for any new building can be issued. The Town of Los Gatos does not approve or imply approval for final alignment or design of these facilities.
65. CURB AND GUTTER REPAIR: The Owner and/or Applicant shall repair and replace to existing Town standards any curb and gutter damaged now or during construction of this project. All new and existing adjacent infrastructure must meet Town standards. New curb and gutter shall be constructed per Town Standard Details. New concrete shall be free of stamps, logos, names, graffiti, etc. Any concrete identified that is displaying a stamp or equal shall be removed and replaced at the Contractor's sole expense and no additional compensation shall be allowed therefore. The limits of curb and gutter repair will be determined by the Engineering Construction Inspector during the construction phase of the project. The improvements must be completed and accepted by the Town before a Certificate of Occupancy for any new building can be issued.
66. DRIVEWAY APPROACH: The Owner and/or Applicant shall install one (1) Town standard residential driveway approach. The new driveway approach shall be constructed per Town Standard Plans and must be completed and accepted by the Town before a Certificate of Occupancy for any new building can be issued. New concrete shall be free of stamps, logos, names, graffiti, etc. Any concrete identified that is displaying a stamp or equal shall be removed and replaced at the Contractor's sole expense and no additional compensation shall be allowed therefore.
67. CONSTRUCTION VEHICLE PARKING: No construction vehicles, trucks, equipment and worker vehicles shall be allowed to park on the portion of any public (Town) streets without written approval from the Town Engineer.
68. CONSTRUCTION TRAFFIC CONTROL: All construction traffic and related vehicular routes, traffic control plan, and applicable pedestrian or traffic detour plans shall be submitted for review and approval by the Town Engineer prior to the issuance of an encroachment, grading or building permit.
69. HAULING OF SOIL: Hauling of soil on- or off-site shall not occur during the morning or evening peak periods (between 7:00 a.m. and 9:00 a.m. and between 4:00 p.m. and 6:00 p.m.), and at other times as specified by the Director of Parks and Public Works. Prior to the issuance of a grading or building permit, the Owner and/or Applicant or their representative shall work with the Town Building Department and Engineering Division Inspectors to devise a traffic control plan to ensure safe and efficient traffic flow under periods when soil is hauled on or off the project site. This may include, but is not limited to provisions for the Owner and/or Applicant to place construction notification signs noting the dates and time of construction and hauling activities, or providing additional traffic

control. Coordination with other significant projects in the area may also be required.
Cover all trucks hauling soil, sand and other loose debris.

70. CONSTRUCTION HOURS: All construction activities, including the delivery of construction materials, labors, heavy equipment, supplies, etc., shall be limited to the hours of 8:00 a.m. to 6:00 p.m., weekdays and 9:00 a.m. to 4:00 p.m. Saturdays, holidays excluded. The Town may authorize, on a case-by-case basis, alternate construction hours. The Owner and/or Applicant shall provide written notice twenty-four (24) hours in advance of modified construction hours. Approval of this request is at discretion of the Town.
71. CONSTRUCTION NOISE: Between the hours of 8:00 a.m. to 8:00 p.m., weekdays and 9:00 a.m. to 7:00 p.m. weekends and holidays, construction, alteration or repair activities shall be allowed. No individual piece of equipment shall produce a noise level exceeding eighty-five (85) dBA at twenty-five (25) feet from the source. If the device is located within a structure on the property, the measurement shall be made at distances as close to twenty-five (25) feet from the device as possible. The noise level at any point outside of the property plane shall not exceed eighty-five (85) dBA.
72. CONSTRUCTION MANAGEMENT PLAN SHEET: Prior to the issuance of any grading or building permits, the Owner and/or Applicant's design consultant shall submit a construction management plan sheet (full-size) within the plan set that shall incorporate at a minimum the Earth Movement Plan, Project Schedule, employee parking, construction staging area, materials storage area(s), construction trailer(s), concrete washout(s) and proposed outhouse location(s). Please refer to the Town's [Construction Management Plan Guidelines](#) document for additional information.
73. WVSD (West Valley Sanitation District): A Sanitary Sewer Clean-out is required for each property at the property line, within one (1) foot of the property line per West Valley Sanitation District Standard Drawing 3, or at a location specified by the Town.
74. SANITARY SEWER BACKWATER VALVE: Drainage piping serving fixtures which have flood level rims less than twelve (12) inches (304.8 mm) above the elevation of the next upstream manhole and/or flushing inlet cover at the public or private sewer system serving such drainage piping shall be protected from backflow of sewage by installing an approved type backwater valve. Fixtures above such elevation shall not discharge through the backwater valve, unless first approved by the Building Official. The Town shall not incur any liability or responsibility for damage resulting from a sewer overflow where the property owner or other person has failed to install a backwater valve as defined in the Uniform Plumbing Code adopted by the Town and maintain such device in a functional operation condition. Evidence of West Sanitation District's decision on whether a backwater device is needed shall be provided prior to the issuance of a building permit.
75. BEST MANAGEMENT PRACTICES (BMPs): The Owner, Applicant and/or Developer is responsible for ensuring that all contractors are aware of all storm water quality measures and that such measures are implemented. Best Management Practices (BMPs) shall be maintained and be placed for all areas that have been graded or disturbed and for all material, equipment and/or operations that need protection. Removal of BMPs (temporary removal during construction activities) shall be replaced at the end of each working day. Failure to comply with the construction BMP will result in the issuance of correction notices, citations, or stop work orders.

76. SITE DESIGN MEASURES: All projects shall incorporate at least one of the following measures:
- a. Protect sensitive areas and minimize changes to the natural topography.
 - b. Minimize impervious surface areas.
 - c. Direct roof downspouts to vegetated areas.
 - d. Use porous or pervious pavement surfaces on the driveway, at a minimum.
 - e. Use landscaping to treat stormwater.
77. EROSION CONTROL: Interim and final erosion control plans shall be prepared and submitted to the Engineering Division of the Parks and Public Works Department. A maximum of two (2) weeks is allowed between clearing of an area and stabilizing/building on an area if grading is allowed during the rainy season. Interim erosion control measures, to be carried out during construction and before installation of the final landscaping, shall be included. Interim erosion control method shall include, but are not limited to: silt fences, fiber rolls (with locations and details), erosion control blankets, Town standard seeding specification, filter berms, check dams, retention basins, etc. Provide erosion control measures as needed to protect downstream water quality during winter months. The Town of Los Gatos Engineering Division of the Parks and Public Works Department and the Building Department will conduct periodic NPDES inspections of the site throughout the recognized storm season to verify compliance with the Construction General Permit and Stormwater ordinances and regulations.
78. DUST CONTROL: Blowing dust shall be reduced by timing construction activities so that paving and building construction begin as soon as possible after completion of grading, and by landscaping disturbed soils as soon as possible. Further, water trucks shall be present and in use at the construction site. All portions of the site subject to blowing dust shall be watered as often as deemed necessary by the Town, or a minimum of three (3) times daily, or apply (non-toxic) soil stabilizers on all unpaved access roads, parking areas, and staging areas at construction sites in order to insure proper control of blowing dust for the duration of the project. Watering on public streets shall not occur. Streets shall be cleaned by street sweepers or by hand as often as deemed necessary by the Town Engineer, or at least once a day. Watering associated with on-site construction activity shall take place between the hours of 8 a.m. and 5 p.m. and shall include at least one (1) late-afternoon watering to minimize the effects of blowing dust. All public streets soiled or littered due to this construction activity shall be cleaned and swept on a daily basis during the workweek to the satisfaction of the Town. Demolition or earthwork activities shall be halted when wind speeds (instantaneous gusts) exceed twenty (20) miles per hour (MPH). All trucks hauling soil, sand, or other loose debris shall be covered.
79. AIR QUALITY: To limit the project's construction-related dust and criteria pollutant emissions, the following the Bay Area Air Quality Management District (BAAQMD)-recommended basic construction measures shall be included in the project's grading plan, building plans, and contract specifications:
- a. All exposed surfaces (e.g., parking areas, staging areas, soil piles, graded areas, and unpaved access roads) shall be watered two times per day, or otherwise kept dust-free.

- b. All haul trucks designated for removal of excavated soil and demolition debris from site shall be staged off-site until materials are ready for immediate loading and removal from site.
 - c. All haul trucks transporting soil, sand, debris, or other loose material off-site shall be covered.
 - d. As practicable, all haul trucks and other large construction equipment shall be staged in areas away from the adjacent residential homes.
 - e. All visible mud or dirt track-out onto adjacent public roads shall be removed using wet power vacuum street sweepers at least once per day, or as deemed appropriate by Town Engineer. The use of dry power sweeping is prohibited. An on-site track-out control device is also recommended to minimize mud and dirt-track-out onto adjacent public roads.
 - f. All vehicle speeds on unpaved surfaces shall be limited to fifteen (15) miles per hour.
 - g. All driveways and sidewalks to be paved shall be completed as soon as possible. Building pads shall be laid as soon as possible after grading unless seeding or soil binders are used.
 - h. Post a publicly visible sign with the telephone number and person to contact at the lead agency regarding dust complaints. This person shall respond and take corrective action within forty-eight (48) hours. The Air District's phone number shall also be visible to ensure compliance with applicable regulations.
 - i. All excavation, grading, and/or demolition activities shall be suspended when average wind speeds exceed twenty (20) miles per hour.
 - j. Vegetative ground cover (e.g., fast-germinating native grass seed) shall be planted in disturbed areas as soon as possible and watered appropriately until vegetation is established.
80. CONSTRUCTION ACTIVITIES: All construction shall conform to the latest requirements of the CASQA Stormwater Best Management Practices Handbooks for Construction Activities and New Development and Redevelopment, the Town's grading and erosion control ordinance, and other generally accepted engineering practices for erosion control as required by the Town Engineer when undertaking construction activities.
81. SITE DRAINAGE: Rainwater leaders shall be discharged to splash blocks. No through curb drains will be allowed. On-site drainage systems for all projects shall include one of the alternatives included in section C.3.i of the Municipal Regional NPDES Permit. These include storm water reuse via cisterns or rain barrels, directing runoff from impervious surfaces to vegetated areas and use of permeable surfaces. No improvements shall obstruct or divert runoff to the detriment of an adjacent, downstream or down slope property.
82. SILT AND MUD IN PUBLIC RIGHT-OF-WAY: It is the responsibility of Contractor and homeowner to make sure that all dirt tracked into the public right-of-way is cleaned up on a daily basis. Mud, silt, concrete and other construction debris SHALL NOT be washed into the Town's storm drains.
83. GOOD HOUSEKEEPING: Good housekeeping practices shall be observed at all times during the course of construction. All construction shall be diligently supervised by a person or persons authorized to do so at all times during working hours. The Owner and/or

Applicant's representative in charge shall be at the job site during all working hours. Failure to maintain the public right-of-way according to this condition may result in penalties and/or the Town performing the required maintenance at the Owner and/or Applicant's expense.

84. PERMIT ISSUANCE: Permits for each phase; reclamation, landscape, and grading, shall be issued simultaneously.
85. COVERED TRUCKS: All trucks transporting materials to and from the site shall be covered.

TO THE SATISFACTION OF THE SANTA CLARA COUNTY FIRE DEPARTMENT:

86. FIRE SPRINKLERS REQUIRED. (As noted on Sheet A-1) An automatic residential fire sprinkler system shall be installed in one- and two-family dwellings as follows: In all new one- and two-family dwellings and existing one- and two-family dwellings when additions are made that increase the building area to more than 3,600 square feet. Exception: One or more additions made to a building after January 1, 2011 that does not total more than 1,000 square feet of building area. An automatic sprinkler system shall be provided throughout all new basements regardless of size and throughout existing basements that are expanded by more than 50%. NOTE: The owner(s), occupant(s) and any contractor(s) or subcontractor(s) are responsible for consulting with the water purveyor of record in order to determine if any modification or upgrade of the existing water service is required. A State of California license (C-16) Fire Protection Contractor shall submit plans, calculations, a completed permit application and appropriate fees to the Santa Clara County Fire Department for review and approval prior to beginning their work. CRC Sec. 313.2 as adopted and amended by LGTC.
87. CONSTRUCTION SITE FIRE SAFETY: (As noted on Sheet A-1) All construction sites must comply with applicable provisions of the CFC Chapter 33 and Santa Clara County Fire Department Standard Detail and Specification S1-7. Provide notations on subsequent plan submittals, as appropriate to the project. CFC Ch. 33.
88. WATER SUPPLY REQUIREMENTS: (As noted on Sheet A-1) Potable water supplies shall be protected from contamination caused by fire protection water supplies. It is the responsibility of the applicant and any contractors and subcontractors to contact the water purveyor supplying the site of such project, and to comply with the requirements of that purveyor. Such requirements shall be incorporated into the design of any water-based fire protection systems, and/or fire suppression water supply systems or storage containers that may be physically connected in any manner to an appliance capable of causing contamination of the potable water supply of the purveyor of record. Final approval of the system(s) under consideration will not be granted by the Santa Clara County Fire Department until compliance with the requirements of the water purveyor of record are documented by that purveyor as having been met by the applicant(s). 2016 CFC Sec. 903.3.5 and Health and Safety Code 13114.7.
89. ADDRESS IDENTIFICATION: (As noted on Sheet A-1) New and existing buildings shall have approved address numbers, building numbers or approved building identification placed in a position that is plainly legible and visible from the street or road fronting the property.

These numbers shall contrast with their background. Where required by fire code official, address numbers shall be provided in additional approved locations to facilitate emergency response. Address numbers shall be Arabic numbers or alphabetical letters. Numbers shall be a minimum of 4 inches (101.6 mm) high with a minimum stroke width of 0.5 inch (12.7mm). Where access is by means of a private road and the building cannot be viewed from the public way, a monument, pole or other sign or means shall be used to identify the structure. Address numbers shall be maintained. CFC Sec. 505.1. Show Drysdale Drive address on future plan submittals.

90. **REQUIRED FIRE FLOW:** The fire flow for this project is 2,500 GPM at 20 psi residual pressure from a single hydrant. As an automatic fire sprinkler system will be installed, the fire flow will be reduced by 50% establishing a required adjusted fire flow of 1,250 GPM at 20 psi residual pressure. Document provided from a local water purveyor confirms required fire flow is available.
91. **EMERGENCY GATE/ACCESS GATE REQUIREMENTS:** (As noted on Sheet A-1) Gate installations shall conform with the Fire department Standard Details and Specification G-1 and, when open shall not obstruct any portion of the required width for emergency access roadways or driveways. Locks, if provided, shall be fire department approved prior to installation. Gates across the emergency access roadways shall be equipped with an approved access device. Show on the plans where the proposed Knox key switch will be located.
92. **FIRE APPARATUS (ENGINE) ACCESS DRIVEWAY REQUIRED:** (As noted on Sheet C.4 of 8) Provide an access driveway with a paved all weather surface, a minimum unobstructed width of 12 feet, vertical clearance of 13 feet 6 inches, minimum circulating turning radius of 36 feet outside and 23 feet inside, and a maximum slope of 15%. Installation shall conform to the Fire Department Standard Details Specifications D-1 and CFC Section 503.